

REQUEST FOR QUOTATIONS

Grit and Screenings Hauling Request for Quotations

Addendum #1 – Site Visit Questions and Answers

Issued: Tuesday, May 7, 2019

Updated Closing Date & Time: 3:00 PM (14:00 hrs) Pacific Time on Friday, May 10, 2019

This addendum shall be read in conjunction with and considered as an integral part of the Request for Quotations. Revisions supersede the information contained in the original Request for Quotations. No consideration will be allowed for any extras due to any Proponent not being familiar with the contents of this Addendum. All other terms and conditions remain the same.

1. Regional District of Nanaimo (RDN) would like to extend the submission deadline for this Request for Quotations (RFQ) to **3:00 pm (Pacific Standard Time) on Friday, May 10, 2019**.

Replace all references for the submission deadline in the Request for Quotations with the new date and time.

2. The RDN would also like to extend the Enquiry Deadline to **Wednesday, May 8, 2019 at 4:00 pm (Pacific Standard Time)**.

Replace all references for the Enquiry Deadline in the Request for Quotations with the new date and time.

GNPCC Site Visit Questions and Answers -May 1, 2019

RDN representatives:

Operations Superintendent

Chief Operator – Greater Nanaimo Pollution Control Centre

Engineering Technologist – Wastewater Services

Purchasing Manager, Finance

Representatives from the following companies in attendance:

DBL Disposal Ltd.

Questions and Answers:

Q1) Could you please confirm the dimensions and requirements for the Roll Off & Roll On Bins

A1) Bins must be 7 foot (wide) by 10 foot (long) by at least 55 inches (4.6 ft) (tall). Bins must be compatible with the loading locations at GNPCC and FCPCC.

Bins must have a lid that can be closed during transport. The lids must be able to be opened at the loading facility to allow bins to be filled while the bins are placed. The contractor must open this lid after delivering a new bin and close and secure the bin lid prior to transport.

The RDN would prefer that the proposed bin lids at GNPCC be similar in function to the FCPCC bin lids (see picture below from Request for Quotations Appendix A – Figure 1).



Q2) It will be difficult to provide a bin cover immediately for the GNPCC Screenings service. Would the RDN accept an interim cover for several months?

A2) Yes, the RDN would accept an interim cover for up to 2 months provided that this cover completely prevents spills during transport and provides for effective odour control.

Q3) Where would access be to the screenings building and grit building after is constructed (estimated to be around August)?

A3) Access will be via the road by the fence at GNPCC by Hammond Bay Road north of the digester.

Q4) When will screenings removal start at GNPCC?

A4) Screenings removal at GNPCC is estimated to commence in mid-May. The exact start date is uncertain due to the GNPCC secondary upgrade construction.

Q5) Please confirm the width between the bin rails in the Screenings building at GNPCC.

A5) The width between the railings is 7 foot 6 inches by 10 foot (see picture below).

