



**REQUEST FOR TENDER No. 21-039**

**Wastewater Services Roof Replacements**

**Addendum 1  
(2 pages)**

**Issued: May 6, 2021**

**Closing Date & Time: on or before 3:00 PM Pacific Time on May 13, 2021**

This addendum shall be read in conjunction with and considered as an integral part of the Request for Tender. Revisions supersede the information contained in the original Tender or previously issued Addendum. No consideration will be allowed for any extras due to any Vendor not being familiar with the contents of this Addendum. All other terms and conditions remain the same.

**Please find enclosed Addendum 1 from Westcoast Roof Inspection Services Ltd.**

Submissions and Questions are to be directed to:

Robert Skwarczynski

Greater Nanaimo Water Pollution Control Centre Chief Operator, Wastewater Services

Email: [rskwarczynski@rdn.bc.ca](mailto:rskwarczynski@rdn.bc.ca)

Questions are requested to be received at least 5 calendar days prior to closing

# ADDENDUM

---

Date: May 6, 2021 Page 1 of 1  
Project: Wastewater Services Roof Replacements  
Locations: Chase River Pump Station, 1174 Island Highway South, Nanaimo, BC, and Greater Nanaimo  
Pollution Control Centre, 4600 Hammond Bay Road, Nanaimo, BC  
Tender #: Request For Tenders No. 21-039

---

## RE: ADDENDUM No. 1

Please note the following changes to the above mentioned Tender which will be known as Addendum No. 1. The content of this addendum will form an integral part of the Contract Documents. All costs associated with this addendum are to be included in the Tender price. Ensure this addendum is acknowledged with your contract documents.

### 1. Chase River Pump Station

- .1 Add 2% Tapered Polyisocyanurate for Crickets between roof drains on the main roof section.

### 2. Dewatering Building

#### .1 The HVAC Units:

- .1 HVAC Units will remain in place on curbs. Install membrane and sheet metal flashing as specified.
- .2 Supply and install new aluminum flashings (Menziess) and new weather-heads for supply lines.
- .3 Include new aluminum flashing and weather-head for existing un-used pipe and weather-head.

#### .2 The Safety Anchor Line Assembly on the replacement roof will be removed.

- .1 Anchors and cables on the existing SBS roof will remain in place.
- .2 Coil up cabling on the existing SBS roof.
- .3 Remove and dispose of anchor posts on the replacement roof.
- .4 Cut off the anchor plate bolts flush with the concrete deck.

Dated: May 6, 2021

Signed: 

**END OF ADDENDUM No. 1**